



# Facility Improvement & Data Optimization (FIDO) Efforts at the NASA NTF

Eric L. Walker & Roman Paryz

Presented at the  
**AIAA SciTech Conference**  
**Aerospace Sciences Meeting (ASM)**

5 - 9 January 2015  
Kissimmee, FL

Subject Category: Test Facilities, Transonic Wind Tunnel  
Key Words: Modifications / Upgrades



NASA Langley Research Center

NTF

# What is FIDO



- **A concentrated, multi-year effort to improve NTF's overall capabilities**
- **An institutionalization of lessons learned from the STARBUKS project (Subsonic Transonic Applied Refinements By Using Key Strategies)**
- **This multi-million dollar effort is making improvements to our**
  - **Accuracy and Validation**
    - Improved repeatability / data quality for results that can be trusted
  - **Productivity**
    - Completing required testing in a timely manner
  - **Reliability**
    - Keep the facility operational without interruption



# STARBUKS Summary

## Accuracy & Validation

- ☑ Data Acquisition System (Test SLATE)
- ☑ Mach Measurement System
- ☑ Facility Automation System
- ☑ Cooling Coil Trailing Edge Fairings
- ☑ Fixed Fairing Extension
- ☑ Alt. Probes Locations (RTD on Cooling Coil)
- ☑ Test Section Visibility
- ☑ Balance Calibrations

## Productivity

- ☑ Cryogenic Active Damper
- ☑ Balance Limit Alarm (BLAMS) Upgrade
- ☑ Inlet Guide Vane (IGV)  $\Delta T$  Mitigation
- ☑ Continuous Pitch

## Reliability

- ☑ High Pressure Air Reducing Station
- ☑ Drive Coupling
- ☑ IGV Hydraulic Pipe Repair

IMPROVED NTF

### Phase I Testing

☑ Check Std  
Test 214

☑ CRM  
Test 215

☑ Completed

### Phase II Testing

☑ Flow  
Calibration  
Test 217

CRM Data Flow Quality  
☑ Test 218

# FIDO Improvements Roadmap

## Accuracy & Validation

- ☐ Tunnel configuration selection
- ☐ Mach stability  $\pm 0.0005$
- ☒ Conditional sampling (off-line)
- ☒ Validate RTD array on cooling coil

## Productivity

- ☐ Mach control methodology
- ☐ 2<sup>nd</sup> throat actuation
- ☐ Conditional sampling (on-line, real-time)
- ☐ Increase access housing heating
- ☐ Optimized nitrogen injection
- ☒ Continuous sweep

## Reliability

- ☐ Liquid nitrogen pump health monitoring
- ☐ Minimize nitrogen system hammering

IMPROVED NTF

### Phase I Testing

✓ Check Std  
Test 219

✓ Flow Survey  
Rake  
Test 216A

✓ Completed

### Phase II Testing

Calibration  
Extension  
Test 220

CRM  
Test 221

Turbulence  
Survey Rake  
Test 216B

# FIDO Projects and Tests



- **5 Major Projects**

- **Test Section Movables (2<sup>nd</sup> Throat)**
  - Tunnel configuration selection
  - Mach control methodology
  - 2<sup>nd</sup> throat actuation
- **Conditional Sampling**
  - Off-line [Complete]
  - On-line real-time
- **Increasing Access Housing Heating**
- **Proportional Liquid Nitrogen (LN2) Injection**
  - Optimized nitrogen injection
  - Minimize nitrogen system hammering
- **LN2 Pump Health Monitoring**

- **5 Experimental Entries**

- **Test 219 Check standard [Pathfinder]**
  - Mach control methodology
  - Continuous sweep optimization
- **Test 216A&B Flow survey rake**
  - Validate RTD array
  - Verify turbulence reduction from STARBUKS [Deferred due to budget]
- **Test 220 Calibration extension**
  - Mach control methodology
- **Test 221 CRM validation**
  - Validation of combined system upgrades



# National Transonic Facility – NTF





## 30 Years of High Reynolds Number RDT&E

### The Highest Reynolds Number Transonic Facility Operating in Air

### The Highest Reynolds Number Transonic Facility Operating Cryogenically



Test Section	8.2 x 8.2 x 25 Feet ( 2.5 x 2.5 x 7.6 meters)	
Pressure	14.7 to 133 psia; 1 to 9.0 atm.; 1.01 to 9.1 bar	
	Air Operations	N <sub>2</sub> Operations
Mach No.	0.2 to 1.05	0.2 to 1.20
Reynolds No. Max	20x10 <sup>6</sup> / ft (65x10 <sup>6</sup> / m)	145x10 <sup>6</sup> / ft (475x10 <sup>6</sup> / m)
Temperature	90° to 150°F (32° to 65°C)	-50° to -250°F (-45° to -157°C)




NASA Langley Research Center

NTF

# Test Section Movables (2<sup>nd</sup> Throat)

Accuracy & Validation, Productivity



- **Improve Mach stability (physical)**
  - Target  $\pm 0.0005$  Mach number for transonic conditions
  - Part of original NTF design for “superior Mach control”
- **Project components**
  - Develop a robust instrumentation package to determine wall position
  - Develop a remote wedge system for the fixed faring to minimize support system induced dynamics
- **Planned to be operational in Summer 2015**
- **Requires calibration extension**




# Conditional Sampling

## Accuracy & Validation, Productivity



- **Improve data quality**
  - Reject data samples that do not meet requirements
- **Off-line: available**
  - Performance penalty due to longer data samples required
  - Need ~2 seconds of valid data
  - May need to acquire 10-12 sec
- **On-line: in development**
  - Stop acquiring data when samples meet specified criteria
  - Alleviates most of performance penalty






$C_D \pm 0.0001$

Avg 1<sup>st</sup> 2 Sec

Conditional Sample  
1<sup>st</sup> 2 Sec

Conditional Sample  
1<sup>st</sup> Valid 2 Sec (of 12)

Test	Run	Mach	TT (deg F)	Q (psf)	ReC (million)	Roll (deg)
218	96	0.850	125.6	1386.5	4.94	0.00
218	97	0.850	127.4	1387.3	4.92	0.00
218	98	0.850	128.0	1386.3	4.91	0.00



$M \pm 0.0005$







# Increasing Access Housing Heating Productivity



- **Target**
  - 50% reduction in model access time
- **Current system**
  - 20 kW convection heater
  - 2 torch heaters (convection)
  - 2 IR lamps for sting base
- **Approach**
  - Replace torch heaters with medium-wave (mw) IR heaters
  - 4 mwIR heaters with independent control using an 4 optical pyrometers for surface temperature measurement
  - New articulating arm structure





# Proportional Liquid Nitrogen (LN<sub>2</sub>) Injection


## Accuracy & Validation, Reliability




- **Current system**
  - 336 injection nozzles controlled by 12 binary (butterfly) valves
  - 8 programmed injection patterns
- **Proposed changes**
  - Replace binary valves with proportional (ball) valves
  - Update the automation hardware
  - Revise control system
  - Incorporate RTD array for fine temperature control
- **Proposed benefits**
  - Optimized LN<sub>2</sub> injection
  - Minimized LN<sub>2</sub> system dynamics
  - Improved reliability of LN<sub>2</sub> system
- **Planned to be operational in Summer 2015**



# Cooling Coil RTD Array



- **Double dual total temperature probes (RTD) have been installed at 9 locations in 21ft x 21ft pattern**
  - 36 temperature sensors
    - 18 for data
    - 18 for control
  - Represents 5ft wing span in the test section



Reference  
Total  
Temperatures





# LN2 Pump Health Monitoring

## Reliability



- **Goal**
  - Make LN<sub>2</sub> system more robust
  - Limit pump trips
  - Measure/predict pump health
- **Current system**
  - Monitoring of 12 accelerometers
  - 6 internal/6 externally mounted
- **Planned changes**
  - Motor current based monitoring of the two largest pumps
  - Consolidate accelerometers and current signals
  - Assess two solutions for trending and analysis
    - Simple spectral analysis with peak frequency recording
    - Data recorder with high level analysis capability



# Check Standard Model (PF1) – Test 219

## Accuracy & Validation, Productivity




### Purpose

- Verify Mach stability for the Mach 0.90 choke configuration of 2<sup>nd</sup> throat used for CRM
  - Determine whether model size affects tunnel choke (PF1 is 70% of CRM in size)
  - Determine the extent of Mach variation benefit as a function of Mach number
- Verify control and data system updates
  - Conditional sampling
  - Continuous pitch/sweep optimization
  - Temporal alignment of balance and reference conditions from new Mach Measurement Sys.
- Gather fluctuating pressure data on test section walls, arc sector, and high speed diffuser to check noise propagation

### Test Conditions

- Mach number:  $0.70 \leq M \leq 0.88$
- Dynamic Pressure:  $766 \text{ psf} \leq Q \leq 1040 \text{ psf}$
- Reynolds number (c):  $2.5 \times 10^6 \leq Re \leq 2.8 \times 10^6$
- Total Pressure: 21.5 psi
- Temperature:  $+120^\circ \text{F}$
- Angle-of-Attack:  $-2^\circ \leq \alpha \leq +4.5^\circ$




# Rake Test 216 A&B

## Accuracy & Validation



- **Purpose**
  - Verify flow reference measurements
  - Evaluate circuit flow line changes on reference conditions and their uniformity
    - Arc-sector fixed fairing extension
    - Cooling coil trailing edge fairings
  - Validate cooling coil RTD array
  - Document improvements to test section flow quality *[T216B only]*
  - Understand flow dynamics
- **Sensors used**
  - Unsteady pressure sensors
  - Hot-wire sensors *[T216B only]*
  - Resistive Temperature Devices
  - Total pressure probes
- **Results**
  - Reference conditions verified
  - RTD array validated
  - Continuous sweep used successfully
  - Dynamic pressure fluctuations documented by Jones AIAA 2015-####
- **Test 216B deferred due to budget**



7ft Flow Survey Rake



# Centerline Pipe Tunnel Calibration Test 220

Accuracy & Validation, Productivity



## Purpose:

- **Extend centerline Mach and buoyancy calibration for use of the 2<sup>nd</sup> throat**
  - Previous testing demonstrated requirement
  - Planned as a correction to the existing calibration
- **Planned for late-Summer 2015**



NASA Langley Research Center

NTF




# Common Research Model Test 221

Accuracy & Validation, Productivity



Planned full system demonstration of FIDO projects: Fall 2015



NASA Langley Research Center

NTF



# Summary



- **Several upgrade projects are in progress at the NASA LaRC National Transonic Facility (NTF) to incorporate lessons learned from the STARBUKS project**
- **This multi-year effort is enhancing NTF's overall capabilities by improving the Accuracy and Validation, Productivity, and Reliability capabilities at the NTF**



# Questions?

